### Fire Wall Testing And Air Leakage Control To Aid In Construction Tolerances And In Litigation

F.ASCE, DFE, D-IBFES, CFCC, CBCP, PT1, NACHI, Therm II, MAE, F.ASCE, F.NAFE efronapfel@byothersllc.com

Thanks to: Robby Schwarz BUILDTankinc robbv@buildtankinc.com

And his permission to incorporate "10 Strategies: Meeting Air Sealing and Code Requirements for Townhouse Area Separation Walls"

Presented by: Edward L. Fronapfel, PE, CBIE, F.ASCE,









Summer Camp XXVII

Twenty-Seventh Westford Symposium on Building Science

### Schedule

0-5 Review of the history of passive fire wall construction in multi-family and commercial applications

5-45 Review of alleged defective work and standard investigation findings from both visual and intrusive testing, review of air-tightening

45-75 Review of testing that was performed and the findings based on a multitude of both proprietary and non-proprietary testing

Q and A


# Learning Objectives: Collaboration of trades and the End Product

Understanding and applying the provisions of 2-hour wall construction

Understanding the observation criteria for quality assurance in fire wall construction

Understanding the impacts of tolerances on the construction of 2-hour walls

Understanding the impacts of air sealant at critical interfaces



#### **Developing Your Conclusions**

NFPA 921 – 4.3.5 and 4.3.6 – Hypothesis

#### **Inductive Reasoning:**


Based on empirical data the investigator has collected through observations, knowledge, training and experience

#### **Deductive Reasoning:**

The investigator does not have a valid or reliable conclusion unless the hypothesis can stand the test of careful and serious challenge.

Compare the Hypothesis
All Known Facts
Body of Scientific Knowledge
Testing of the Hypothesis
 Lab, Calculations, Modeling
Disprove the Hypothesis (find out why it is not true by each specific component in the assembly)

This will prevent "Confirmation Bias" that is formed solely on supporting data






### The Fire Wall

- Interdisciplinary Requirement Not just the Architect
- Civil Engineer Laying out the buildings per setbacks
- Architect Type of Use, Layouts, Materials, Assemblies
- Structural Type of Structure, the materials
- Mechanical/Plumbing/Electrical Systems that interrupt or pass
- Building Science Assemblies that work, reduce air losses, control the environment
- Structure Sound Resistance Reduction in Air Loss





What constitutes the UL fire rated assembly?



# Combine your fire prevention needs with your air barriers

- Newport Partners a consulting firm headquartered Davidsonville MD coordinated research on behalf of HUD/PD&R
- Field research was conducted at Thrive Home Builders townhouse project in Wheat Ridge Colorado
- NFPA managed an Advisory Group
- This session is designed to inform stakeholders of the key issues involved in building safe and energy efficient in ASWs in townhouses
- Our goal is to provide strategies to make the process easier and ultimately more affordable

RESOURCE DEVELOPMENT | Newport Partners LLC

## **Newport Partners, LLC**

 A Strategy Guide for Air-Sealed Townhome Area Separation Walls That Meet Energy and Building Codes

#### **Executive Summary**

Townhomes are an important part of the housing market, especially when it comes to affordability. They provide living space and some outdoor space, often at a lower relative cost to homebuyers than single-family detached homes. With smaller lots and shared interior walls, or area separation walls (ASWs), townhomes are often more cost-effective to construct than single-family detached homes (exhibit 1). However, the tension between air sealing requirements in the International Energy Conservation Code (IECC) and requirements for fire-rated assemblies between townhomes in the International Residential Code (IRC) has caused significant challenges in both construction and code enforcement (exhibit 2).

Exhibit 1. Townhome Area Separation Walls Under Construction



Photo Credit: Newport Partners

Exhibit 2. Code Tension Between Air Sealing Requirements in the IECC and Requirements for Fire-Rated Assemblies Between Townhomes in the IRC



A Strategy Guide for Air-Sealed Townhome Area Separation Walls That Meet Energy and Building Codes




### Two One Hour and One Two Hour

Because the (2) separate assemblies provide the same level of fire protection between units (ie, Double 2-hour walls versus the Single 2-hour wall), the subject of this memo discusses the equivalency of the two separate systems of which, under section 104.2.7 "Modifications," the building department properly approved.

The construction of the Single 2-hour, in lieu of the Double 1-hour, was approved because the 2 constructions were documented as equivalent in the 2003 International Residential Code (IRC), of which the City had knowledge of by the time the Double 1-hour wall was constructed but after the permits were issued (See R317.2 – 2003 IRC attached).

In short, the fire-resistive separation walls, as constructed, were deemed to be equivalent to the originally designed wall, as well as met the intent of the minimum requirements of the 1997 Uniform Building Code, because of the knowledge of the 2003

International Residential Code. As for the 1-hour fire resistive assemblies between the garages, these also are acceptable based on the UBC formal interpretation of section 503.2 (See 503.2 UBC interpretation attached).



Area Separation Walls (Sections 504.6.2., 504.6.3., and 504.6.4.)

UBC 504.6.2. requires that the required area separation walls in R-1 VN buildings be constructed with a minimum of 2-hour rated assemblies.

When a 2-hour rated assembly is used, Section 504.6.4. requires that the area separation wall extend above the roof 30-inches, or the 2-hour wall is allowed to terminate at the bottom side of the roof deck provided additional measures are taken to install 1-hour fire-resistive construction within 5-feet of the area separation wall termination (see Section 504.6.4.).

Section 504.6.3. requires that the separation walls extend to the outer face of the exterior wall of the building unless there are enclosed horizontal projecting elements such as porches or balconies.

In these cases, the area separation wall must extend to the end of the horizontal projecting element, but only if it is enclosed



## GA-620-2019 GYPSUM AREA SEPARATION FIREWALLS

#### Introduction

Gypsum Area Separation Firewall systems provide the advantages of both fire-resistance and noise reduction between neighboring townhouses and other attached dwelling units. Gypsum Area Separation Firewalls are efficient, nonloadbearing, 2-hour fire resistance rated gypsum panel systems that can provide code compliant STC ratings exceeding 60.





Fig 1 – Typical Gypsum Area Separation Firewall Construction

### NFPA 221 (1929-2021)


## Standard for High Challenge Fire Walls, and Fire Barrier Walls

- 6.2 Structural Stability:
- 6.2.1 Fire walls shall be designed and constructed to remain stable after collapse of the structure due to fire on either side of the wall.
- 6.2.2 fire walls constructed in compliance with the requirements of Sections
- 6.3, 6.4, 6.5 shall be deemed to provide the required stability.
- 6.4.2 Framework
- 6.4.2.1 Structural framing on either side of the wall shall line up horizontally and vertically and shall support the roof.
- 6.4.2 The framework on each side of the fire wall shall be continuous and tied together through the wall.
- 6.4.2.3 The frame work on each side shall be designed so that it resists the maximum lateral pull that can be developed due to the framework collapse on the opposite side.
- 6.5 Double Fire Walls
- 6.5.1 A double frame wall consists of two back to back walls
- 6.5.2 There shall be no connections, other than to the flashing between the walls.
- 6.5.3 Each fire walls shall be supported laterally by the building frame on its respective side and shall be independent of the fire wall and framing on the opposite side.



#### 2-Hour Area Separation Wall System

The 2-hour area separation wall system is a 2-hour fire wall consisting of 2" (50.8 mm) light-gauge steel H-Studs that secure two layers of 1" (25.4 mm) shaftliner panels friction-fit between studs and a minimum 3/4" (19.1 mm) air space on each side.



#### AREA SEPARATION WALL LIMITING HEIGHTS

 1. Roof
 9. ASW Clip

 2. Rim Joist
 10. Wood Stud

 3. Top Plate
 11. Horizontal Blocking


 4. Two Layers
 12. First Floor


4. Two Layers 12. Finish Floor
eXP® Shaftliner 13. Subfloor

5. H-Stud 14. Minimum 3/4" Air Space

Double C-Track (Back-to-Back)
 XP® Gygsum Boards
 Foundation

8. Fire Blocking 1" eXP\* Shaftliner or Mineral Wool






2. 1" eXP® Shaftliner or Shaftliner XP®

3. 2" H-Stud

4. 1/2" Fire-Shield C™ Gypsum Batten


\*Battens not required when 3/4" air space is maintained



NGC Construction Guide | 199


#### ROOF JUNCTION DETAIL

- 1. Roof Deck
- 2. 2x2 Wood Ledger
- 3. 2" C-Track
- 4. Gypsum Board or Mineral Wool Fire Blocking
- 5. ASW Clip
- 6. Minimum 3/4" Air Space
- 7. 1" eXP Shaftliner or Shaftliner XP
- 8. 5/8" Fire-Shield Gypsum Board, 4' each side when roof deck is not constructed with fireretardent treated wood




#### ROOF PARAPET DETAIL

- 1. Roof Deck
- 2. 2" C-Track
- 3. Gypsum Board or Mineral Wool Fire Blocking
- 4. Minimum 3/4" Air Space
- 5. ASW Clip
- 6. 1" eXP Shaftliner or Shaftliner XP




#### EXTERIOR WALL JUNCTION DETAIL

- 1. Siding
- 2. 5/8" eXP Fire-Shield Sheathing
- 3. Insulation
- 4. 2x4 Wood Stud
- 5. 2" C-Track
- 6. Gypsum Board or Mineral Wool Fire Blocking
- 7. Minimum 3/4" Air Space
- 8. 1" eXP Shaftliner or Shaftliner XP
- 9. ASW Clip
- 10.2" H-Stud
- 11. Gypsum Board




#### EXTERIOR WALL INTERSECTION DETAIL

- Sidina
- 2. Plywood or OSB Sheathing
- 3. Insulation
- 4. 2x4 Wood Stud
- 5. 2" C-Track
- 6. Gypsum Board or Mineral Wool Fire Blocking
- 7. Minimum 3/4" Air Space
- 8. 1" eXP Shaftliner or Shaftliner XP
- 9. ASW Clip
- 10.2" H-Stud
- 11. Gypsum Board




#### FOUNDATION DETAIL

- 1. Gypsum Board
- 2. 2x4 Wood Plate
- 3. Insulation
- 4. Minimum 3/4" Air Space
- 5. 1" eXP Shaftliner or Shaftliner XP
- 6. Sealant
- 7. 2" C-Track
- 8. Fasteners 24" o.c. Max.



#### FLOOR INTERSECTION DETAIL

- 1. Subfloor
- 2. Sealant
- 3. 2" Wood Plate
- 4. Gypsum Board
- 5. Insulation
- 6. Minimum 3/4" Air Space
- 7. Rim Joist
- 8. Gypsum Board or Mineral Wool Fire Blocking
- 9. 1" eXP Shaftliner or Shaftliner XP
- 10. ASW Clip
- 11. 2x4 Wood Stud
- 12. Ceiling



## **Gypsum Association**



## GA-620-2019 GYPSUM AREA SEPARATION FIREWALLS

#### Introduction

Gypsum Area Separation Firewall systems provide the advantages of both fire-resistance and noise reduction between neighboring townhouses and other attached dwelling units. Gypsum Area Separation Firewalls are efficient, nonloadbearing, 2-hour fire resistance rated gypsum panel systems that can provide code compliant STC ratings exceeding 60.

Note: Always use back-to-back C-runners between courses in Gypsum Area Separation Firewalls. Do not substitute a single H-stud for the specified back-to-back C-runners.


Erect shaft liner panels and H-studs in the same manner as for the first section of wall, except that starting and ending procedures may vary depending on the exterior wall intersection detail.

- 13. Install code approved fire blocking on both sides of the Gypsum Area Separation Firewall at each floor and the roof line. Fire blocking should fit tightly between the truss and framing area to the shaft liner panel.
- 14. At top floor, the Gypsum Area Separation Firewall may either extend to the top of a parapet wall or terminate at the underside of the roof deck. When terminating at the underside of the roof deck, the roof decking material for 4 ft (1220 mm) on either side of the wall shall be either Fire Retardant Treated plywood or gypsum panels.
- 15. At roof intersection the walls are capped-off with C-runners.

### Fire and Sound

#### 2-Hour Fire Rating

Design Reference: UL U373, UL U375, ULC W312, WHI GP/WA 120-04, cUL U373, cUL U375, GA ASW 0810



#### 65-69 STC Sound Trans.


Test Reference: RAL TL 10-291

Two layers 1" (25.4 mm) DensGlass Shaftliner inserted in H-Studs 24" (610 mm) o.c. Min. 3/4" (19 mm) air space on both sides must be maintained between liner panels and adjacent framing.

Sound Tested with 2" (51 mm) x 4" (102 mm) stud wall with 1/2" (12.7 mm) ToughRock gypsum wallboard each side of assembly and 3-1/2" (89 mm) fiberglass insulation in stud space both sides.

#### 2-Hour Fire Rating

Design Reference: WHI 495-0743



#### 35-39 STC Sound Trans. Est.

Part. Thickness: 3" (76 mm)

Two layers 1" (25.4 mm) DensGlass Shaftliner inserted in H-Studs 24" (610 mm) o.c. Metal covered using 6" (152 mm) wide 1/2" (12.7 mm) DensArmor Plus® Fireguard C® interior panels or 1/2" (12.7 mm) ToughRock Fireguard C® gypsum board.


CAUTION: For product fire, safety and use information, go to buildgp.com/safetyinfo.

For latest information and updates: 7 Technical Service Hotline 1.800.225.6119 or www.gpgypsum.com



#### **GYPSUM ASSOCIATION**

#### Fig 8 – Roof Intersection with Parallel Roof Trusses






DensGlass® Shaftliner Area Separation Walls

#### **Details** continued


#### Attic-Adjacent to Trusses\*




\*Only applies to accessible attic space. Not needed for inaccessible attic space. See special conditions #7 on page 6.


DensArmor Plus® Fireguard C® panels or 1/2" (12.7 mm) ToughRock® Fireguard C® or 5/8" (15.9 mm) DensArmor Plus® Fireguard® or 5/8" (15.9 mm) ToughRock® Fireguard X® or 1" (25.4 mm) DensGlass® Shaftliner panels


## CFM/SQFT of Unit Envelope Area




## Compartmentalization




















#### When one is next to the other

Horizontal Separation Vertical Separation Mechanical Separation


Reductions – Sprinklers! Activation! Smoke Control!

Maintenance, Repairs and Replacements (Code changes)

Passive is easy to provide without having to engage the future owners



## **Guarded**



## **Guarded Testing is not cost effective!**



## **Air Sealing Separation Walls**

#### GA-620-2019 GYPSUM AREA SEPARATION FIREWALLS

#### Air Sealing Area Separation Walls

Air sealing area separation walls to reduce leakage between units and between the unit and any outside areas where the wall is off-set to meet energy code requirements is becoming a standard practice. Air leakage is measured via a blower door test, which pressurizes the unit, and measurements are taken to calculate the loss per unit area of wall. When a unit fails (i.e. leaks more than allowed by the code), the most common means of reducing air leakage is to seal all cracks, gaps and voids in all walls along the perimeter of a unit to reduce leakage paths. Such gaps, cracks and voids are at the foot and the head of the wall along the C-channels, at seams in the wall along the H-studs, and at intersections with other walls and the ceiling.

NOTE: For a complete discussion on air leakage and energy code requirements, refer to Field Testing of Compartmentalization Methods for Multifamily Construction authored by Kohta Ueno and Joseph Lsitburek, March 2015, as part of the United States Department of Energy's Build America Program.

Many material technologies are available on the market that will effectively seal gaps, cracks and voids. Traditional sealants/caulking materials, spray-applied sealants and membranes, mastics, self-adhered membranes, tapes and spray foams are among just a handful of the technologies available that may prove the best choice in any one application.

Care should be taken when selecting materials for air sealing area separation firewalls. These walls often serve multiple functions, but their intended first purpose is as a fire-resistive barrier. Air sealing materials must therefore be third-party listed and meet the criteria of the pertinent ASTM, UL, or other international standard, or be code compliant as a fire-resistive/fire blocking material. The material must not compromise the fire-rating of the wall.

Field Testing of Compartmentalization Methods for Multifamily Construction



#### Field Testing of Compartmentalization Methods for Multifamily Construction

K. Ueno and J.W. Lstiburek Building Science Corporation

March 2015

#### 2.2 Fire-Resistance Rated Assemblies Air Leakage

Some practitioners have examined the issue of air leakage associated with fire-resistance rated assemblies or area separation walls in multifamily buildings. A typical assembly is the Underwriters Laboratories (UL) U347/U373/U336 2-hour rated assembly.

Holton and Prahl (2005) examined the issue of air leakage at these fire-resistance rated assemblies (area separation walls) in multifamily buildings (such as side-by-side townhomes). They noted that poor thermal performance (specifically, air leakage) has negative results for energy efficiency and comfort. One example was air leakage from the party wall into a vented (unconditioned) attic, resulting in heat loss and ice dam issues. Many party wall designs call out

for an air space between the fiberglass batt stud bay insulation and the 1-in. gypsum shaft liner board core, resulting in an air leakage path that can be connected over multiple floors. The authors questioned whether this air gap is actually necessary for fire performance. Many fire-resistance rated walls provide both interior-to-interior and interior-to-exterior separation (because planes shift between units): this condition increases the risk of air leakage.

## **EERE Findings**

At several interior walls under the vented/unconditioned attic, noticeable air leakage was visible at the top plate (Figure 34 and Figure 35, keyed to "D" in Figure 23). Unfortunately, this indicates that the interior top plate detail (Figure 8) was not executed correctly or consistently.



Figure 34. Interior wall under attic (third floor), Unit 6702

This area was inspected in another unit's attic (Unit 6704; Figure 57). The joints appeared to be sealed with expanding foam where they were inspected; however, access is difficult, so quality control issues are unsurprising.





Figure 57. Vaulted attic and separation wall conditions, Unit 6704

The exterior was examined in the morning with an infrared camera (Figure 58); there was no sign of gross air leakage in the attic at the area separation wall. This would have been manifested as a warm thermal "plume" at the party wall, or significant snow melt/ice damming at the area



#### Field Testing of Compartmentalization Methods for Multifamily Construction

K. Ueno and J.W. Lstiburek Building Science Corporation

March 2015

#### 4.7 Air Leakage Locations: Area Separation Wall Details

Several of the observed air leaks were associated with details at the area separation walls/demising walls. A plan of two adjacent middle units is shown in Figure 47, providing a map of some of the following observations. These area separation wall air leaks were found in multiple units; the plan in Figure 47 is meant to show typical connections between two middle units.




Figure 47. Plan of two adjacent middle units (first floor), with key locations highlighted

separation wall. However, heat loss from the house would be diluted by outdoor air from attic ventilation.


Heat loss and snow melt caused by area separation wall leakage are worse if the stud bay cavity is extended into the attic (unlike these units), creating a "chimney" to direct interior heat to the roof sheathing.

## IECC and the Building Thermal Envelope



### **BUILDING THERMAL ENVELOPE.**

The basement walls, exterior walls, floors, ceiling, roofs and any other building element assemblies that enclose conditioned space or provide a boundary between conditioned space and exempt or unconditioned space.




https://energyrecovery.com.au/MVHR/BuildingAirtightness

# AEROBARRER




Dwelling Unit	A	В	С	D	E	F
Aero Barrier Applied	У	Ν	Υ	N	Υ	Ν
Blower door after Aero Barrier Applied (A,C,E)		7.32 ACH50		<b>5.67</b> ACH50		3.73 ACH50
Blower door Pre-Aero Barrier (some air sealing performed)	<b>4.96</b> ACH50	5.97 ACH50	6.23 ACH50	<b>4.81</b> ACH50	<b>6.44</b> ACH50	3.76 ACH50
Blower door After Aero Barrier	1.64 ACH50	1.50 ACH50	1.88 ACH50	1.53 ACH50	1.67 ACH50	1.60 ACH50
Final Code Blower door	2.19 ACH50	2.39 ACH50	2.75 ACH50	2.05 ACH50	2.34 ACH50	2.02 ACH50







Dwelling Unit	A	В	C	D	E
Aero Barrier	У	N	Υ	N	Y
Blower door after Aero Barrier Applied (A,C,E)		7.28 ACH50		<b>6.74</b> ACH50	
Blower door Pre-Aero Barrier (some air sealing performed)	4.63 ACH50	<b>7.24</b> ACH50	6.43 ACH50	6.62 ACH50	<b>5.10</b> ACH50
Blower door After Aero Barrier	1.83 ACH50	1.80 ACH50	1.90 ACH50	1.70 ACH50	1.59 ACH50
Final Code Blower door	2.88 ACH50	3.00 ACH50	2.54 ACH50	2.64 ACH50	2.31 ACH50







#### 5 Analysis and Recommendations

#### 5.1 Summary of Air Leakage Results

A summary of the unguarded/nonnulled and guarded/nulled testing is shown in Table 7 (with results in terms of ACH50), and Table 8 (with CFM50/ft² enclosure).

Table 7. Unguarded and Guarded Air Leakage Test Results, With ACH50

Unit	Notes	Ungu	arded	Guarded	
Unit	Notes	CFM50	ACH50	CFM50	ACH50
6700	End-improved + taped		3.8	953	3.4
6702	Mid-improved + taped	1329	5.5	1057	4.4
6704	Mid-conventional	1255	5.2	1004	4.2
6706	6706 Mid-improved 6708 End-improved		5.6	1085	4.5
6708			3.9	989	3.5

Table 8. Unguarded and Guarded Air Leakage Test Results, With CFM50/ft<sup>2</sup> Enclosure

		Ung	guarded	Guarded	
Unit	Notes	CFM50	CFM50/ft <sup>2</sup> Enclosure*	CFM50	CFM50/ft <sup>2</sup> Enclosure*
6700	End-improved + taped	1085	0.22	953	0.20
6702	Mid-improved + taped	1329	0.31	1057	0.24
6704	Mid-conventional	1255	0.29	1004	0.23
6706	Mid-improved	1330	0.31	1085	0.25
6708	End-improved	1113	0.23	989	0.20

<sup>\*</sup> This conversion assumes all enclosure surface area, including adiabatic walls.

In both the unguarded and guarded testing, no units met the 3 ACH50 target of the 2012 IECC. As discussed earlier, when this target is calculated in terms of surface area-normalized leakage, it is stringent for these small three-story townhome units (0.16–0.17 CFM50/ft²). But the fact that the units do not meet the requirements in the nulled test suggests that the issues are not isolated to area separation wall problems alone (although it might also be due to area separation wall cavity leakage to the exterior).

The results show no improvement associated with taping the exterior sheathing; in fact, some cases were slightly worse. The "conventional" construction middle unit performed better than the "improved" detail middle units.

The intent was to leave the tapes in place and have the builder document the performance over time, after temperature cycling and exposure. However, house wrap was applied to the entire building the next day, so no results were obtained. This experiment could be repeated at other jobsites or at a controlled exposure site.





Figure 74. Test application of two types of adhesive sheathing tape



Figure 75. Test application of two types of adhesive sheathing tape

The literature indicates that taped sheathing is useful for achieving very stringent airtightness targets (e.g., 1 ACH50 and lower). However, if there are more substantial leaks—as was the case here—the difference will likely be difficult to discern.

The units either achieved or were close to the normalized 0.30 CFM50/ft<sup>2</sup> enclosure standard recommended by Lstiburek (2005b) for multifamily units, the target proposed by Maxwell (2014), and the revised target for ASHRAE 62.2 (Brennan 2014). The units would likely consistently achieve the 0.30 CFM50/ft<sup>2</sup> standard with some additional air sealing details and/or technologies (e.g., interior spray-applied latex sealant).

Table 9. Unguarded and Guarded Air Leakage Test Results, With ΔCFM50

Unit	Notes	Unguarded CFM50	Guarded CFM50	Δ CFM50	Δ CFM50 %
6700	End-improved + taped	1085	953	-132	-12%
6702	Mid-improved + taped	1329	1057	-271	-20%
6704	Mid-conventional	1255	1004	-250	-20%
6706	Mid-improved	1330	1085	-245	-18%
6708	End-improved	1113	989	-125	-11%

The shifts from unguarded to guarded testing were 11%–12% for the end units and 18%–20% for the middle units. This is consistent with leakage caused by connections at the area separation walls, and a reduction proportional to the one versus two area separation walls. However, testing indicated that this nulling was not perfect and that outside air was drawn into the area separation wall framing cavity from the exterior.



#### Field Testing of Compartmentalization Methods for Multifamily Construction

K. Ueno and J.W. Lstiburek Building Science Corporation

March 2015

### **Aero Barrier**

### Eliminating caulking or gaskets

- Around electrical outlets and
- Other drywall penetrations
- Along ASW and ceiling spaces
- To vented attics.


















Image from Building America Report – 1508. Kohta Ueno, Joe Lstiburek. March






It all about sealing the gap with cost-effective options that don't impact compliance









### What occurs – Code Derived to Risk







### Material Testing to Assembly Testing

### **5 Shaft Liner Assemblies**

- U336 UNITED STATES GYPSUM CO
- U347 NATIONAL GYPSUM CO
- U366 CERTAINTEED GYPSUM INC
- U373 GEORGIA-PACIFIC GYPSUM L L C
- U375 AMERICAN GYPSUM CO

### Standard Test Methods for Fire Tests of Building Construction and Materials


- The test is used to measure and describe the response
   of materials and assemblies to heat and flame under
   controlled conditions for a specified time period
- When required, the fire exposure is followed by the application of a standard fire hose stream applied in accordance with ASTM E2226
- Hose stream test assesses the impact, erosion, and cooling effects of a fire fighting like hose stream on a burned assembly

# ASTM E 119: Fire Tests of Building Construction and Materials


#### • SECTION 703 FIRE-RESISTANCE RATINGS AND FIRE TESTS


**703.2 Fire-resistance ratings.** The *fire-resistance rating* of building elements, components or assemblies shall be determined in accordance with the test procedures set forth in ASTM E 119 or UL 263 or in accordance with Section 703.3 (alternative methods for determining fire resistance).


- ASTM E 119 Acceptance Criteria:
- 4.3 The test standard provides for the following:
- 4.3.1 For walls, partitions, and floor or roof test specimens:
- 4.3.1.1 Measurement of the transmission of heat.
- 4.3.1.2 Measurement of the transmission of hot gasses through the test specimen.
- 4.3.1.3 For loadbearing elements, measurement of the load carrying ability of the test specimen during the test exposure




- 1. Subfloor
- 2. Sealant
- 3. 2" Wood Plate
- 4. Gypsum Board
- 5. Insulation
- 6. Minimum 3/4" Air Space
- 7. Rim Joist
- **8.** Gypsum Board or Mineral Wool Fire Blocking
- 9. 1"Fire-Shield Shaftliner
- **10.** 2x4 Wood Stud
- 11. ASW Clip
- 12. Ceiling









#### 4. Significance and Use

4.2 The test exposes a test specimen to a standard fire controlled to achieve specified temperatures throughout a specified time period. When required, the fire exposure is followed by the application of a specified standard fire hose stream applied in accordance with Practice E2226. The test provides a relative measure of the fire-test-response of comparable building elements under these fire exposure conditions.

The exposure is not representative of all fire conditions because conditions vary with changes in the amount, nature and distribution of fire loading, ventilation, compartment size and configuration, and heat sink characteristics of the compartment. Variation from the test conditions or test specimen construction, such as size, materials, method of assembly, also affects the fire-test-response. For these reasons, evaluation of the variation is required for application to construction in the field.

# ASTM E 119: Fire Tests of Building Construction and Materials

4.4 The tests standard does not provide the following:

4.4.1 Information as to performance of test specimens constructed with components or lengths other than those tested.

4.4.2 Evaluation of the degree by which the test specimen contributes to the fire hazard by generation of smoke, toxic gases, or other products of combustion.

4.4.3 Measurement of the degree of control or limitation of

the passage of smoke or products of combustion through the test specimen.

4.4.4 Simulation of the fire behavior of joints between building elements such as floor-wall or wall-wall, etc., connections.

4.4.5 Measurement of flame spread over the surface of test specimens.

4.4.6 The effect on fire-resistance of conventional openings in the test specimen, that is, electrical receptacle outlets, plumbing pipe, etc., unless specifically provided for in the construction tested. Also see Test Method E814 for testing of fire stops



### Test Speciman

#### Test Specimen

- 5.1 The test specimen shall be representative of the construction that the test is intended to assess, as to materials, workmanship, and details such as dimensions of parts, and shall be built under conditions representative of those applied in building construction and operation. The physical properties of the materials and ingredients used in the test specimen shall be determined and recorded.
- 5.2 The size and dimensions of the test specimen specified herein shall apply for classifying constructions of dimensions within the range employed in buildings. When the conditions of use limit the construction to smaller dimensions, the dimensions of the test specimen shall be reduced proportionately for a test qualifying them for such restricted use




### The Test





### Constructing the walls



NGC Construction Guide™ | National Gypsum Company

#### **Fire and Sound Selector**

#### Fire and Sound Ratings

#### FIRE RATINGS

Fire resistance is the ability of an assembly constructed in a laboratory to contain a fire in a carefully controlled test setting for a specified period of time. ASTM E119, Standard Test Methods for Fire Tests of Building Construction and Materials, is the test standard for determining the fire-resistance rating of partitions, ficer-ceiling assemblies, roof-ceiling assemblies, beams and columns. Fire tests may be conducted at any one of several recognized facilities.

Fire-resistance ratings regressed the results of tests on assembles made up of specific materials in a specific configuration. When selecting construction designs to meet certain fire-resistance regularments, caution must be used to ensure that each component of the assembly is the one specified in the test. Further, precading should be taken that assembly procedures are in accordance with those of the tested assembly. Per copies of specific tests, catll \*800-NATIONAL (628-4662).

#### SOUND RATINGS

Gygsum board assemblies are laboratory tested to establish their sound attenuation characteristics. Airborne sound insulation is reported as the Sound Transmission Class (STC), impact noise, tested on floor-ceiling systems only, is reported as the Impact insulation Class (IC), ASTM 890, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements, is the test standard for airborne sound reduction. The test measures the sound transmission loss at 16 one-third octave frequencies to generate a single-number accustical rating.

When selecting systems based on laboratory performance ratings, it should be understood that field conditions such as flanking paths or air leaks caused by design or workmanship can reduce acoustical performance. For this reason, Gold Bond Building Products, LLC cannot guarantee the performance ratings of specific assemblies in the field.

To achieve maximum sound isolation from an assembly, follow published construction details completely. Use non-hardening acoustical sealant at penetrations and floor, ceiling and wall intersections to grevent flanking gaths for sound.



#### GENERAL NOTES REGARDING FIRE-RATED ASSEMBLIES

- Unless otherwise specified, the face layers of all assembles, except those with predecorated surfaces or exterior gyosum sheathing, shall have joints taped and fastener heads treated (minimum Level 2 as appeched in 6A-214, Levels of Finish for Gypsum Panel Products, Base layers in mutti-layer assembles shall not be required to have joints or fasteners taped or covered with joint compound.
- When not specified as a component of a fire-tested wall or partition assembly, mineral fiber, glass fiber, or celluloss fiber insulation of a thickness not exceeding that of the stud depth shall be permitted to be added within the stud cavity.
- 3. In floor-ceiling or roof-ceiling assembles, the addition or deletion of mineral wool or glass fiber insulation in the concealed space between the ceiling membrane and the floor or roof structure could possibly reduce the fire-resistance rating. The addition of insulation to any one- or two-hour fire-resistance rated floor-ceiling or roof-ceiling assembly is permitted provided that one additional layer of gypsum boar of the same type specified in the design is added to the ceiling.
- Additional layers of gypsum board are permitted to be added to any assembly.
- Stud sizes specified in wood- or steel-stud assemblies are minimums.
- Stud spacings specified in wood- or steel-stud assemblies are maximums.
- Beam, joist and truss dimensions specified in floor-ceiling or roof-ceiling assemblies are minimums.
- Beam, joist and truss spacings specified in floor-ceiling or roof-ceiling assemblies are maximums.
- The distance between parallel rows of studs in wood- or steel-stud assemblies are minimums.
- Ceilings supported directly from structural members are permitted to be suspended provided the in place stiffness is equivalent to the tested assembly.

#### Construction







### **The Problem**











### Common Claims in Construction Defects

- Mixing of Products
- Breaches
- Use of H-clips instead of back to back C-Clips
- Lack of ASW Clips (Height)
- Lack of Floor/Ceiling Closure
- Lack of Proper Fasteners
- Lack of ¾ Inch Air Space

- What variables matter?
- What information is available from manufacturer's regarding their exact testing?
- Multiple Burns Required to determine each variable in relation to loss of functional use.
- And so, we began.....































### Breaches


- a. Fire-Resistive Wall Assembly ASWs and ASW Panels with Gaps:
  - Noted locations where the metal ASW components were not provided.:
  - Discontinuous ASWs and ASW panels with gaps."

ISSUE:

During installation of the ASW System, the vertical H-Studs and or the C-Runner track can be damaged or gaps between framing members can mistakenly be built into the wall (up to 1" maximum). Either of these defects voids the intended 2-hour fire rating.

REPAIR:


- Fill the damaged area or the gap/hole with 3M Fire Barrier Sealant CP 25 WB+ fire caulk
- Center over the fire caulking a section of metal flat strap minimum 4" in width by 18" long (14 gauge)
- Secure metal flat strap to H-Stud or C-Runner Track with 1/2" Tek #8 self-drilling screws, spaced 6" on center
- Apply fire caulk around the perimeter of the metal flat strap
- Duplicate the metal flat strap patch on opposite side of wall



### Number of Screws and Type



- 1 1/4" Screw Wood
- 3/8-Inch Pan Head Channel




### Define Life Safety – Potential?

- Q. Okay. So of those 108 units, that's not
- 3 **100 -- it's not 195 units, correct?**
- 4 A. No. But as we've already gone over this,
- 5 they are very consistent in certain aspects, and those
- 6 aspects are also consistent with the design that we
- 7 understand was to be constructed. So I think it's
- 8 very likely that the balance of the units are
- 9 constructed in a similar fashion.
- 10 Q. Okay. So if you're not sure how long it
- 11 will last --
- 12 A. It actually doesn't matter, as long as
- 13 it's -- it's less than two hours, which is the minimum
- 14 code requirement.

- 15 Q. Okay. And you've given an opinion that
- 16 you believe that the fire wall assembly is -- and I'll
- 17 use <mark>-- you believe that there is a life safety issue</mark>
- 18 with the construction of the fire-resistive assembly
- 19 separating the dwelling units at this project?
- 20 A. Yes.
- 21 Q. And what do you mean by life safety?
- 22 A. Well, the -- what is safe is defined by
- 23 the building code, and that's the minimum standard of
- 24 safety. And these walls do not meet that standard.
- 25 So in a fire event, particularly these areas where

#### 120

- 1 there's missing walls, those walls will not protect
- 2 life or property as intended by the code. So that, in
- 3 my opinion, that's a life safety issue.













#### **Conclusions before your Conclusions** (Ipse Dixet)

NFPA 921 – 4.3.9 and 4.3.10 – Bias

#### **Expectation Bias:**

Reaching a premature conclusion without having examined all the relevant data. The forensic observer uses a premature determination to dictate the investigation, processes, analysis and ultimately the conclusion.

They chose to use only the data that supports the pre-formed conclusion, without the use of scientific methods and review of all potentially relevant data.

#### **Confirmation Bias:**

Different hypothesis may be compatible with the same data. The Scientific Method should be provided to disprove the hypothesis. Confirmation Bias solely relies on the supporting data, and neglects non-supportive data.

The conclusions made from the hypothesis and testing should be based when rigorous testing has disproved the hypothesis

### Mixing of Products


#### Fire-Resistive Wall Assembly – Gypsum Manufacturer Substitutions

- The architectural plans reviewed specify Underwriters Laboratories LLC (UL) Design U347 and GA File No. ASW 1005 for construction of the area separation walls at the Project and includes a detail indicating the construction of those assemblies."
- The panels used at the Project are not approved for use in the specified UL347 assembly nor do they match the panels indicated on the architectural plans
- At this time, it is unclear if the contractor received approval to utilize the materials placed for the assembly specified or if an alternative assembly was utilized. Therefore we are requesting documentation from the Builder demonstrating code-compliant ASW system installed at the Project, considering the gypsum panels installed at the Project are not acceptable for the ASW design specified by the Architect and approved by building department.

- The failure to utilize the proprietary product does not equate to a failure to perform the intended function of a 2-hour firewall assembly.
- We agree as forensic engineers that testing can be provided to determine the walls' performance, and such testing has been done over the last few years under our direction.

### Plaintiffs Conclusion:

- It is our opinion that the code-required 2-hour fire rating is compromised when the construction of the ASW assembly is closer than 3/4-inch to the framing and/or missing/non-compliant clips/channels are installed. Proximity to framing is important during a fire event to ensure that heat transfer across the ASW assembly does not cause combustion in an adjacent unit for the specified 2-hour rating of the assembly.
- Without aluminum clips in areas designated by the UL tested assemblies and the construction documents, the framing supporting the shaft wall can fail and cause failure of the firewall. During a fire event, the aluminum clips on the fire side will melt (as designed), disconnecting the wood framing from the ASW assembly, while the aluminum clips on the non-fire side will provide the structural support for the firewall assembly. Without the required aluminum clips on both sides, the system cannot perform as intended



From Claimant's Expert

### Fire-Resistive Wall Assembly – Utilization of H Channels on Horizontal and 3/4-Inch Separation

- The referenced assemblies indicate for horizontal seams to be joined with back-toback "C" channels and vertical seams to be joined with H channels. These components are also indicated by the manufacturers of the ASW panels used at the Project.
- At all locations observed, non-compliant steel members used to join the horizontal panel joints at the ASW. The metal ASW components were not provided. As indicated above, during observations of the ASW assemblies at the Project, the following were noted:


- In order to provide performance-based and ultimately approved testing of as-built assemblies, to properly evaluate the issues through ICC NTA, LLC (ICC NTA) test, and review and determine the performance of the as-constructed shaftliner area separation wall assembly as generally described in UL listed assemblies 336, 347, 366, 373, and 375.
  - The wall assembly was evaluated in general accordance with the following:
    - ASTM E119-18c "Standard Test Methods for Fire Tests of Building Construction and Materials"
    - ANSI/UL 263-2018 "Standard for Safety for Fire Tests of Building Construction and Materials"
    - ASTM E2226-15b "Standard Practice for Application of Hose Stream"

#### Fire-Resistive Wall Assembly – Aluminum Clip Installation

- Aluminum clips were utilized to attach the gypsum board "H" channels to the framing members. The clips were noted to be manufactured by Phillips Manufacturing Company (Phillips).
- UL's Design No. U347 and all GA specified area separation walls also require aluminum angle clips securing the area separation wall to the adjacent framing. The clips are also specified by the manufacturers of the ASW panels used at the Project. The previously referenced GA-600-2003 Fire Resistance Design Manual states:


"At intermediate floors metal floor/ceiling track shall be installed back-to-back to secure the top of the lower section of the partition to the bottom of the next section being installed."

- Missing and/or non-compliantly installed aluminum clips were noted to occur throughout the Project.
- Phillips indicates proper clip installation and fasteners in their publication titled, Installation Recommendations, H-Stud Area Separation Wall Assemblies, Version 1.1, dated 2013.
  - "Secure Phillips ASW Clips to the studs with one 3/8" Type S pan head screw through the short leg of the clip. Secure the clip to the wood framing with one 8d nail or 1-1/4" Type W screw through the long leg of the clip."




Excerpt from GA, GA-600-2003 Fire Resistance Design Manual Sound Control Gypsum Systems, 17th Edition, Dated April 2003.

### Proposed Assemblies



Drawing No. 1
Fiberglass faced, gypsum Area Separation panel layout



Drawing No. 2

Skeleton 2x4 framing – 16-in. O.C. with 12-in. edge-to-center on end

#### Appendix A - Photographs



Photo No. 1
ASW Installation with support wall framing



Photo No. 2
Insulation shelf constructed and attached to wall assembly


Table 1. Material Description.					
Material	Manufacturer	Received On			
2 ft × 10 ft × 1-in. Sheetrock® Glass-Mat Shaft liner	U.S. Gypsum	09/26/2022			
2 in. × 10-ft H-Studs (No. 25 MSG Galv. Steel)	ClarkDietrich	09/22/2022			
2 in. × 10-ft C-Runner (No. 25 MSG Galv. Steel)	ClarkDietrich	09/22/2022			
2 in. × 2 in. × 2.5-in. AB36 ASW aluminum angle clips (0.063 in. thick)	ClarkDietrich	09/22/2022			
2 in. × 4 in. × 10-ft Douglas Fir framing studs	N/A	09/09/2022			
3 in. × 6-in. MP36 Mending/Gusset plates	Simpson Strong-Tie	09/22/2022			
³/s-in. Type A Pan Head screws, 1½-in. Type W screws and 16d 3½-in. long shank nails	Various	09/21/2022			
Great Stuff Pro Foam sealant	Dow	09/23/2022			
Insulation for perimeter of test assembly	N/A	Stock			

#### 3.1 Sample Description

The wall assembly consisted of two wood stud framed walls on each side of a shaft liner ASW and had overall dimensions of  $10 \times 10$  ft. The assembly was constructed following the *Burn Test Assembly Construction Specifications* provided by BUILDTank, Inc., which are included in Appendix E.






Figure 1. Thermocouple Layout.

### Construction of the Walls





## Detailing









Photo No. 5 Unexposed side of Test Assembly





Photo No. 1 ASW Installation



• • • • • • • • •

## Constructed Assemblies



Connections and Convection

### Control

- 7 Control
- 7.1 Fire-Resistance Test:
- 7.1.1 *Time-Temperature Curve:*
- 7.1.1.1 The furnace temperatures shall be controlled to follow the standard time-temperature curve shown in Fig. 1.The points on the curve that determine its character are:
- 1000°F (538°C) at 5 min
- 1300°F (704°C) at 10 min
- 1550°F (843°C) at 30 min
- 1700°F (927°C) at 1 h
- 1850°F (1010°C) at 2 h
- 2000°F (1093°C) at 4 h
- 2300°F (1260°C) at 8 h or over
- 7.1.1.2 For a more detailed definition of the time-temperature curve, see Appendix X1




FIG. 1 Time-Temperature Curve



## 3 Minutes



## 10 minutes



## 15 Minutes




## 20 Minutes



## 27 Minutes Consumption - Purple



Similar to all Results 25 to 30 Minutes Combustibles Consumed



## 32 Minutes - Green



Photo No. 10
Deflection of ASW at mid-height of wall assembly

## Deflection

## Edge of Chamber Review



1922 National Board of Fire Underwriters Hose Stream Test

Pioneers to the Insurance Organization and Fire Prevention Codes

Impact, Erosion and Cooling






2 Hour Hose Stream – Did Not Pass – so...


## 120 Minutes





Remove for Hose Stream Test (2 Hour)






• ASTM E119 "Standard Test Methods for Fire Tests of Building Construction and Materials" burn test. Screenshot immediately after 2-hour furnace burn test. Note: wall assembly passed the 2-hour burn test.

## Hose Stream







Successful Pass of Hose Stream







## Hypothesis Disproven

Exemplar photograph of wood framing after 2-hour burn test with shaft wall panels removed showing no damage or charring to wood framing on non-burn side due to breaching or heat transfer.

# Timing Review of Performance

#### 4.4 Test Results

At 11:04 AM, the burners were ignited, and the furnace temperature was controlled following the standard time-temperature curve for a period of 120 minutes.

#### TEST OBSERVATIONS

1:10 2x4 skeleton framing ignition 3:07		TEST OBSERVATIONS		
3:07 Lumber framing self-extinguished 11:24 Insulation shelf dilapidating 24:30 Support wall beginning to fall away from ASW 32:00 Lumber still attached at base of wall up to insulation shelf 46:00 Lumber at base of wall still present, rest of lumber has fallen away 1:00:00 No change to exposed face, 1-1/2-in. deflection at center of wall 1:08:00 No change to exposed face 1:10:00 Deflection: 2-1/4-in. at center of wall, midheight 1:20:00 No change to exposed face to report 1:30:00 Deflection: 3-1/2-in. deflection at midheight 1:40:00 No change to exposed face of wall assembly 1:45:00 3-3/4-in. of deflection at midheight 1:50:00 No changes to exposed face	0:00	Ignitors Lit, Test Started		
11:24 Insulation shelf dilapidating 24:30 Support wall beginning to fall away from ASW 32:00 Lumber still attached at base of wall up to insulation shelf 46:00 Lumber at base of wall still present, rest of lumber has fallen away 1:00:00 No change to exposed face, 1-1/2-in. deflection at center of wall 1:08:00 No change to exposed face 1:10:00 Deflection: 2-1/4-in. at center of wall, midheight 1:20:00 No change to exposed face to report 1:30:00 Deflection: 3-1/2-in. deflection at midheight 1:40:00 No change to exposed face of wall assembly 1:45:00 3-3/4-in. of deflection at midheight 1:50:00 No changes to exposed face	1:10	2x4 skeleton framing ignition		
24:30  Support wall beginning to fall away from ASW  32:00  Lumber still attached at base of wall up to insulation shelf  46:00  Lumber at base of wall still present, rest of lumber has fallen away  1:00:00  No change to exposed face, 1-1/2-in. deflection at center of wall  1:08:00  No change to exposed face  1:10:00  Deflection: 2-1/4-in. at center of wall, midheight  1:20:00  No change to exposed face to report  1:30:00  Deflection: 3-1/2-in. deflection at midheight  1:40:00  No change to exposed face of wall assembly  1:45:00  3-3/4-in. of deflection at midheight  No changes to exposed face	3:07	Lumber framing self-extinguished		
ASW  32:00 Lumber still attached at base of wall up to insulation shelf  46:00 Lumber at base of wall still present, rest of lumber has fallen away  1:00:00 No change to exposed face, 1-1/2-in. deflection at center of wall  1:08:00 No change to exposed face  1:10:00 Deflection: 2-1/4-in. at center of wall, midheight  1:20:00 No change to exposed face to report  1:30:00 Deflection: 3-1/2-in. deflection at midheight  1:40:00 No change to exposed face of wall assembly  1:45:00 3-3/4-in. of deflection at midheight  1:50:00 No changes to exposed face	11:24	Insulation shelf dilapidating		
32:00  Lumber still attached at base of wall up to insulation shelf  46:00  Lumber at base of wall still present, rest of lumber has fallen away  1:00:00  No change to exposed face, 1-1/2-in. deflection at center of wall  1:08:00  No change to exposed face  1:10:00  Deflection: 2-1/4-in. at center of wall, midheight  1:20:00  No change to exposed face to report  1:30:00  Deflection: 3-1/2-in. deflection at midheight  1:40:00  No change to exposed face of wall assembly  1:45:00  3-3/4-in. of deflection at midheight  1:50:00  No changes to exposed face	24:30	Support wall beginning to fall away from		
insulation shelf  46:00  Lumber at base of wall still present, rest of lumber has fallen away  1:00:00  No change to exposed face, 1-1/2-in. deflection at center of wall  1:08:00  No change to exposed face  1:10:00  Deflection: 2-1/4-in. at center of wall, midheight  1:20:00  No change to exposed face to report  1:30:00  Deflection: 3-1/2-in. deflection at midheight  1:40:00  No change to exposed face of wall assembly  1:45:00  3-3/4-in. of deflection at midheight  1:50:00  No changes to exposed face		ASW		
46:00  Lumber at base of wall still present, rest of lumber has fallen away  1:00:00  No change to exposed face, 1-1/2-in. deflection at center of wall  1:08:00  No change to exposed face  1:10:00  Deflection: 2-1/4-in. at center of wall, midheight  1:20:00  No change to exposed face to report  1:30:00  Deflection: 3-1/2-in. deflection at midheight  1:40:00  No change to exposed face of wall assembly  1:45:00  3-3/4-in. of deflection at midheight  1:50:00  No changes to exposed face	32:00	Lumber still attached at base of wall up to		
lumber has fallen away  1:00:00  No change to exposed face, 1-1/2-in. deflection at center of wall  1:08:00  No change to exposed face  1:10:00  Deflection: 2-1/4-in. at center of wall, midheight  1:20:00  No change to exposed face to report  1:30:00  Deflection: 3-1/2-in. deflection at midheight  1:40:00  No change to exposed face of wall assembly  1:45:00  3-3/4-in. of deflection at midheight  1:50:00  No changes to exposed face		insulation shelf		
1:00:00  No change to exposed face, 1-1/2-in. deflection at center of wall  1:08:00  No change to exposed face  1:10:00  Deflection: 2-1/4-in. at center of wall, midheight  1:20:00  No change to exposed face to report  1:30:00  Deflection: 3-1/2-in. deflection at midheight  1:40:00  No change to exposed face of wall assembly  1:45:00  3-3/4-in. of deflection at midheight  1:50:00  No changes to exposed face	46:00	Lumber at base of wall still present, rest of		
deflection at center of wall  1:08:00 No change to exposed face  1:10:00 Deflection: 2-1/4-in. at center of wall, midheight  1:20:00 No change to exposed face to report  1:30:00 Deflection: 3-1/2-in. deflection at midheight  1:40:00 No change to exposed face of wall assembly  1:45:00 3-3/4-in. of deflection at midheight  1:50:00 No changes to exposed face		lumber has fallen away		
1:08:00 No change to exposed face 1:10:00 Deflection: 2-1/4-in. at center of wall, midheight 1:20:00 No change to exposed face to report 1:30:00 Deflection: 3-1/2-in. deflection at midheight 1:40:00 No change to exposed face of wall assembly 1:45:00 3-3/4-in. of deflection at midheight 1:50:00 No changes to exposed face	1:00:00	No change to exposed face, 1-1/2-in.		
1:10:00 Deflection: 2-1/4-in. at center of wall, midheight  1:20:00 No change to exposed face to report  1:30:00 Deflection: 3-1/2-in. deflection at midheight  1:40:00 No change to exposed face of wall assembly  1:45:00 3-3/4-in. of deflection at midheight  1:50:00 No changes to exposed face		deflection at center of wall		
height  1:20:00 No change to exposed face to report  1:30:00 Deflection: 3-1/2-in. deflection at midheight  1:40:00 No change to exposed face of wall assembly  1:45:00 3-3/4-in. of deflection at midheight  1:50:00 No changes to exposed face	1:08:00	No change to exposed face		
1:20:00 No change to exposed face to report  1:30:00 Deflection: 3-1/2-in. deflection at midheight  1:40:00 No change to exposed face of wall assembly  1:45:00 3-3/4-in. of deflection at midheight  1:50:00 No changes to exposed face	1:10:00			
1:30:00 Deflection: 3-1/2-in. deflection at midheight 1:40:00 No change to exposed face of wall assembly 1:45:00 3-3/4-in. of deflection at midheight 1:50:00 No changes to exposed face		height		
height 1:40:00 No change to exposed face of wall assembly 1:45:00 3-3/4-in. of deflection at mid-height 1:50:00 No changes to exposed face	1:20:00	No change to exposed face to report		
1:40:00 No change to exposed face of wall assembly 1:45:00 3-3/4-in. of deflection at mid-height 1:50:00 No changes to exposed face	1:30:00	Deflection: 3-1/2-in. deflection at mid-		
1:45:00 3-3/4-in. of deflection at mid-height 1:50:00 No changes to exposed face		height		
1:50:00 No changes to exposed face	1:40:00	No change to exposed face of wall assembly		
and an angle of an	1:45:00	3-3/4-in. of deflection at mid-height		
1.55:00 No changes to report	1:50:00	No changes to exposed face		
1.55.65	1:55:00	No changes to report		
1:57:00 Flaming still at bottom plate of wall	1:57:00	Flaming still at bottom plate of wall		
assembly		assembly		
2:00:00 Burners extinguished; end of fire exposure	2:00:00	Burners extinguished; end of fire exposure		

<sup>\*</sup>Tabular and graphical data can be found in Appendix B

#### HOSE STREAM OBSERVATIONS

0:00	Hose Stream Started		
2:20	Fully developed projection of water,		
	Hose stream test concluded		

## Heat transfer through the channels considered?




Table 3. Summary of Thermocouple Data.

TC	Initial Temperature	Maximum Temperature	Temperature Rise
1	70 °F	188 °F	118 °F
2	69 °F	647 °F	579 °F
3	71 °F	223 °F	153 °F
4	69 °F	370 °F	302 °F
5	70 °F	193 °F	123 °F
6	70 °F	182 °F	112 °F
7	70 °F	504 °F	434 °F
8	71 °F	719 °F	648 °F
9	71 °F	236 °F	165 °F
Average	70 °F	323 °F	253 °F

## Graphical Representation

#### Data




Figure No. 1




Figure C-1. Unexposed Surface Temperature vs. Time.




Figure No. 2

## Summary of Tests


Table 1 Summary of Fire Wall Assembly Test Results						
Fire Wall Test Assembly	ASTM E119	ASTM E2226-15b	Reference ICC Test			
	Burn Test	Hose Stream Test	Report			
	Results	Results				
	(PASS/FAIL)	(PASS/FAIL)				
1. 3/8-inch air gap	PASS	PASS	1			
2. Zero air gap	PASS	PASS	2			
3. Zero air gap with	PASS	FAIL*(2 Hour)	3, 4			
horizontal "H" track						
and insulation at wall						
4. Zero air gap with	PASS	PASS	5			
horizontal "H" track						
with angle clips at top,						
middle, and bottom						
of wall						

- ICC-NAT No. B110220-28
- 2. ICC-NAT No. B010821-52
- 3. ICC-NAT No. B081621-68
- 4. ICC-NAT No. B081621-68A
- 5. ICC-NAT No. B081621-68B

\*Wall assembly retested and passed during B081621-68B







## Strategy 1: Adopt the 2021 IECC for Air Tightness Tradeoffs

## **R402.4.1.2 Testing**

■ The *building* or *dwelling unit* shall be tested for air leakage. The maximum air leakage rate for any building or dwelling unit under any compliance path shall not exceed 5.0 air changes per hour or 0.28 cubic feet per minute (CFM) per square foot  $[0.0079 \text{ m}3/(\text{s} \times \text{m}2)]$  of dwelling unit enclosure area.

 Potentially an R405 Building Performance and R406 Energy Rating Index Compliance Strategy

## **Tradeoff**

- A trade off refers to putting something more in one assembly so you can put something less in another
- HOWEVER, in the IECC's case the energy performance scale remains balanced

 You can tradeoff R-values, U-values, air tightness, duct leakage, etc. depending on the compliance path you are using




- The prescriptive code requires 3 ACH50 in CZ5
- The 3 silver balls balanced the energy equation because they represent better windows, higher R-values, and reduced duct leakage than is required by the IECC
- Therefore, I traded off poor air tightness performance for better windows, R-values, and duct leakage

## **Tradeoff**



## How it really works in the Field

- The blue ball represents
  - Attic insulation R38
  - No slab edge insulation R0
  - No Continuous Insulation
- The prescriptive R-value path says in CZ5 you must
  - R60 attic Insulation
  - R10 Slab Edge Insulation
  - R5 continuous insulation
- The 3 silver balls balanced the energy equation because they represent better windows, air tightness, and reduced duct leakage than is required by the IECC
- Therefore, I traded off LESS ...... for MORE .......









**Strategy 2: Adopt 2021 IECC Compartmentalization Test** 

## **R402.4.1.2 Testing**




■ The *building* or *dwelling unit* shall be tested for air leakage. The maximum air leakage rate for any building or dwelling unit under any compliance path shall not exceed 5.0 air changes per hour or <u>0.28 cubic feet per</u> minute (CFM) per square foot  $[0.0079 \text{ m}3/(\text{s} \times \text{m}2)]$  of dwelling unit enclosure area.

Exception: When testing individual dwelling units, an air leakage rate not exceeding 0.30 cubic feet per minute per square foot [0.008 m3/(s × m2)] of the dwelling unit enclosure area,

- Attached single and multiple family building dwelling units.
- Buildings or dwelling units that are 1,500 square feet (139.4 m2) or smaller.


## CFM/SQFT of Unit Envelope Area



## Conclusion

- Six of the ten strategies provided in this guide are regulatory in nature
- Address tension between Energy Codes and Fire Code
  - Model code amendments
  - Local adoption amendments
  - Additional testing
  - Using existing solutions in the code
  - Broad acceptance
- The Energy Code is a Life Safety Code
- Next Steps





Strategy 3: Add Air Tightness Tradeoffs to 2012, 2015, 2018, IECC

## Amend the code during adoption

2012 IECC

Add Language from 2021 IECC

Limited to R405

Consider amending to include R406

2015 IECC

Add language from 2021 IECC

Stringent ERI Targets Have Limited Use of this Path.


Consider amending R406 to IECC 2018 levels 2018 IECC

Add language from 2021 IECC

## Amend the code during adoption


Be careful how you amend the air leakage requirements in the IECC

- R405 and R406 are performance compliance alternatives
- If you allow 5 ACH50 you have to do something more somewhere else
- If not, it is a role back



# Strategy 4: Amend Residential Code with Options from International Building Code

- Ability to amend the IRC with options listed in the 2018 or 2021 IBC
- The IBC allows six alternative options for demonstrating compliance with fire-rated assemblies
- This Strategy is intended to allow builders, designers, or code officials flexibility to use equivalent approaches while saving the effort and cost of additional testing



## Strategy 4: IBC 703.3 Options



1: Fire-Resistance Designs

Documented to be consistent with E119 or UL263 by Approved Sources

2: Prescriptive Designs

Based on IBC 721/ a guide for building fire rated assemblies

3: Calculations

Based on IBC 722/calculated fire rated assembly

4: Engineered Analysis

Based on comparison to assembly tested to ASTM E119 or UL263

5: Alternative Protection Methods

Based on IBC 104.11/approved equivalent alternative

6: Fire-Resistance Designs


Certified by Approved Agency/code official

# Strategy 5: Amend the Code for Additional Materials



### **IRC Section R302 Fire-Resistant Construction**

- Language could be added to section R302.2 Townhouses
  - R302.2.1 double walls and R302.2.2 common walls,
  - "For the purposes of this code, caulks and sealants may be added to the tested common wall for air sealing purposes."
- The code is not altering ASTM E119 or UL 263 testing
  - It is allowing additional materials to be added to the tested wall
  - Performance criteria for the sealant materials, to ensure fire safety, should be spelled out
  - Air sealants could be allowed but limited in amount or application by the code








# Strategy 6: Redefine the Common Wall Area

## 2021 IRC Section R302.2.2 Common Wall



#### Exception:

 Common walls are permitted to extend to and be tight against the inside of the exterior walls if the cavity between the end of the common wall and the exterior sheathing is filled with a minimum of two 2- inch nominal thickness wood studs.

# **Strategy 7: Test a Broad Class of Materials Nonproprietary Approach**

**Testing** 

Sealant

Applies to Sealants in Category

Applies to any Rated Wall Using that Sealant

## R302.4 Dwelling unit rated penetrations



- Penetrations of wall or floor-ceiling assemblies required to be fireresistance rated in accordance with Section R302.2 or R302.3 shall be protected in accordance with this section.
- R302.4.1.2 Penetration firestop system. Penetrations shall be protected by an approved penetration fire stop system installed as tested in accordance with ASTM E814 or UL 1479
- R302.8 Foam plastics. For requirements for foam plastics, see <u>Section R316</u>
- R302.9 Flame spread index and smoke-developed index for wall and ceiling finishes
- **R302.9.4** Alternative test method. As an alternative to having a flame spread index of not greater than 200 and a *smoke-developed index* of not greater than 450 where tested in accordance with <u>ASTM E84 or UL 723</u>

## **IRC R316**

R316.3.1 Foam plastic insulation 4 inches thick or less. Foam plastic insulation installed at 4 inches (102 mm) in thickness or less shall have a flame spread index of not more than 75 and a smokedeveloped index of not more than 450 where tested in the maximum thickness and density intended for use in accordance with ASTM E84 or UL 723.

roduct Information Sheet



For General Purpose Building Envelope Air Sealing



#### **TESTING**

#### **Applicable Standards**

Great Stuff Pro™ Gaps & Cracks meets the following standards:

- ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials
- ASTM E814 (modified) Standard Test Method for Fire Tests of Through Penetration Fire Stops
- CAN/ULC S102 Method of Test for Surface Burning Characteristics of Building Materials and Assemblies

#### Notice

Great Stuff Pro™ Gaps & Cracks complies with Underwriters Laboratories, Inc. (UL) Classification, Classified as a sealant: see UL R13655.

**Great Stuff Pro™ Gaps & Cracks** complies with the following evaluation reports:

- ICC-ES ESR-1961 (US only)
- CCMC R13074 (CAN only)

Contact your DuPont sales representative or local authorities for state/provincial and local building code requirements and related acceptances.

#### CF 812 WD low-pressure door and window foam

Ultimate ● ● ● ●



Low-pressure foam for air-sealing, filling and insulating doors and windows without warping the frames or jambs

From \$37.25

Compare



Ultimate ● ● ● ●



Helps reduce the spread of flames and smoke in residential type V-B and commercial nonrated construction

From \$37.75

Compare





Foam Systems

## CF-AS CJP All Seasons Crack and Joint Insulating Filler Foam

#### **Product Description**

CF-AS CJP All Seasons Crack and Joint Pro is a high performance, high yield polyurethane foam for filling around penetrations and general gap/crack applications in non fire-rated assemblies. This product is ideal for reducing air, sound, dirt, and water infiltration. CF-AS CJP complies with ASTM C 1620, the industry's first specification on aerosol foam sealants. **NOT FOR USE AS A FIRESTOP.** 

#### **Applications For Use**

- Pipe / cable penetrations
- Blank opening gaps / cracks
- HVAC ducts
- Electrical junction boxes

- · Base plate cracks
- Concrete formwork voids
- · Metal decking seams
- General insulating

#### Testing / Approvals

- UL 723
- ASTM C 1620
- ASTM E 90
- ASTM E 283

- ASTM G 21
- UL 1715
- EPA Method 24
- ICC ES ESR 2179

#### **Technical Data**



## **Example: Test Two-Part Foam**



# Strategy 8: Additional testing of individual UL assemblies

This is a proprietary approach testing a specific assembly with specific materials





## **New Burn Testing for Air Sealing**




- Spray Polyurethane Foam Alliance Coordinated Burn Testing
- 7 sealant products were tested using UL 94, a Standard for Testing of Flammability of Plastic Materials
  - All seven products were tested, and all passed
- One sealant was selected as representative and tested in a full-scale UL263/ASTM E119
  assembly burn test
  - Probable that it was the worst performer in the small-scale test?
  - This product passed
- UL agreed that any product passing the small-scale test will be considered as passing the UL263/ASTM E119 large-scale test
- The sealant manufacture must follow through with listing in the BXUV guide and all have not done that. Probably due to additional UL fees
- If another manufacture wants to be listed, they have to fund and pass the small-scale test and reimburse the project sponsors through SPFA for a portion of the large-scale testing cost

<u>BXUV.Gernaral Provisions - Fire-resistance Ratings - ANSI UL 263 UL Product iQ.pdf</u>

## Shaft Liner Assemblies Allowing Air Sealing

## **Updated December 2020**

- U336 UNITED STATES GYPSUM CO
- U347 NATIONAL GYPSUM CO
- U366 CERTAINTEED GYPSUM INC
- U373 GEORGIA-PACIFIC GYPSUM L L C
- U375 AMERICAN GYPSUM CO



**SECTION B1-B1** 

SECTION B1-B1

CONFIGURATIONS B and D EXPOSED TO FIRE FROM EITHER SIDE

## **BXUV Language**

8. Caulking and Sealants\* — (Optional - Intended for use as an air barrier - Not intended to be used as fire blocking) - A bead of sealant applied around the partition perimeter in the 3/4 in. air space between wood framing (Item 4) and shaftliner panels(Item 3) to create an air barrier.

- DUPONT DE NEMOURS, INC. Great Stuff Gaps & Cracks, Great Stuff Pro Gaps & Cracks, Great Stuff Pro Window & Door
- ICP ADHESIVES & SEALANTS INC Handi-Foam Fireblock, Handi-Foam Fireblock West, and Fast Foam Fireblock



 \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.





## **Installation Process**

# Not spelled out in the BXUV Guide

#### Option #1

- Air seal gap
- Place Fire Stop material on top

#### Option #2

■ Place solid gypsum in <sup>3</sup>⁄<sub>4</sub>-1" gap and air seal





Strategy 9:
Field Solution
with
Innovative
Technology





#### PROJECT OVERVIEW

#### PROJECT

3-Story Rowhomes

#### BUILDER

Thrive Home Builders

#### CONTRACTOR

Rocky Mountain AeroBarrier

#### LOCATION

Wheat Ridge, CO

#### RESULTS

Pre-leakage: 5 ACH50

Post-Leakage: 1.6 ACH50

Reduction: 70%

#### Thrive Home Builders Eliminates Stress of Meeting Code with AeroBarrier

Home builders in the greater Denver area deal with exacting air tightness levels.

While some builders might avoid cities with strict enforcement of low air tightness levels, Thrive Home Builders has turned this challenge into an opportunity. In fact, continuous innovation has differentiated Thrive locally and established it as a nationally recognized pioneer.

"We felt it was important to build a brand around energy-efficient homes," said Bill Rectanus, Thrive's Vice President of Home Building Operations. "Making it an option for homeowners doesn't work. But they will pay for a better home. We made energy efficiency a brand standard, regardless of price point."

As a result, every new Thrive home is designed to meet the highest standards, including LEED\*, EPA Indoor airPLUS, Zero Energy Ready Homes, and Energy Star\*. This has fueled innovation at Thrive – innovation focused on better ways to create healthy, energyefficient homes within these standards.



In addition to sound and odor mitigation, AeroBarrier ensures air from each garage doesn't infiltrate any of the homes.

Bill Rectanus – Vice President of Home Building Operations Thrive Home Builders













Image from Building America Report – 1508. Kohta Ueno, Joe Lstiburek. March



Strategy 10: Add Fire Sprinklers

## Fire Sprinklers

- Fire sprinkler system reduces the requirement for 2-hour separation wall down to a 1-hour wall
- What are the issues with 1-hour walls?
  - Needed on both sides
- Jurisdictions my allow for a reduction of the number of fire hydrants in a community if fire sprinklers are installed which could offset innovative air sealing techniques
- Issues with fire sprinklers and the IECC



# 2021 IECC Table R402.4.1.1 Air Barrier, Air Sealing, and Insulation Installation

**IECC** 2021

- New language in Component Sections:
  - Rim Joist
  - Basement, crawls space and slab foundations
  - Shaft Penetrations
  - Narrow cavities
  - Garage separation
  - Recessed lighting
  - Plumbing wiring or other obstructions
  - Footnote b
    - Air barrier and insulation full enclosure is not required in unconditioned/ventilated attic spaces and at the rim joist

#### TABLE R402.4.1.1 AIR BARRIER AIR SEALING AND INSULATION INSTALLATION

COMPONENT	AIR BARRIER CRITERIA	INSULATION INSTALLATION CRITERIA
General requirements	A continuous air barrier shall be installed in the building envelope.	Air-permeable insulation shall not be used as a sealing material.
	Breaks or joints in the air barrier shall be sealed.	
Ceiling/attic	The air barrier in any dropped ceiling or soffit shall be aligned with the insulation and any gaps in the air barrier shall be sealed.  Access openings, drop down stairs or knee wall doors to unconditioned attic spaces shall be sealed.	The insulation in any dropped ceiling/soffit shall be aligned with the air barrier.
Walls	The junction of the foundation and sill plate shall be sealed.  The junction of the top plate and the top of exterior walls shall be sealed.  Knee walls shall be sealed.	Cavities within corners and headers of frame walls shall be insulated by completely filling the cavity with a material having a thermal resistance, <i>R</i> -value, of not less than R-3 per inch. Exterior thermal envelope insulation for framed walls shall be installed in substantial contact and continuous alignment with the air barrier.

# Table 402.4.1.1 Component – Concealed Sprinklers

## IECC

#### **Air Barrier Criteria**

#### When required to be sealed, concealed fire sprinklers shall only be sealed in a manner that is recommended by the manufacturer. Caulking or other adhesive sealants shall not be used to fill voids between fire sprinkler cover plates and walls or ceilings

#### **Insulation Installation Criteria**















## Fire Sprinklers and air leakage?





https://www.multihousingnews.com/post/rehau-upgrades-residential-fire-sprinkler-system-with-fitting-technology/

## Conclusions: The Summary Version

Although the assemblies are not compliant with strict UL requirements, they in fact do not represent any life-safety issue.

- Clips Matter 5 feet O.C.
- Horizontal Restraint Required
- Fuel Source is likely eliminated very quickly in a two-hour scenario = reality of risk to occupants or structure
- Separation of Structure matters (one side falls)
- Hose test likely unrealistic for attic separation structure salvage during fire fighting operations

- Clips do not burn away (melt)
- Combustibles do not provide alternate fuel source on the nonexposed side
- Fire Retardant products at boundaries will provide protection. On the exposed sides, fire will not be contained, so this is limited to the interstitial space discussions.
- Construction Defect Claims can be sorted into variables of risk, and repairs do not require a full removal and reconstruction.

## Conclusion

- Six of the ten strategies provided in this guide are regulatory in nature
- Address tension between Energy Codes and Fire Code
  - Model code amendments
  - Local adoption amendments
  - Additional testing
  - Using existing solutions in the code
  - Broad acceptance
- The Energy Code is a Life Safety Code
- Next Steps





## Thank you

Edward L. Fronapfel, PE, CBIE, F.ASCE, F.NAFE...

efronapfel@byothersllc.com 303-229-2200