

COLD & VERY COLD

CLIMATES

**Energy Efficiency** 

and Renewable Energy

### **O**VERVIEW

The design of the Concord Cape began in August of 2008. Architects and engineers at BSC developed the drawing set and specifications for the high performance custom home to be built in Concord, Massachusetts. The house is a Cape Cod style design with 5 bedrooms, 4 full bathrooms, 2 stories plus a finished basement. It is built into an existing neighborhood close to public transportation, restaurants, shops and other community resources. BSC worked closely with the homeowner to design a house that combined the desired design aesthetic, both interior and exterior, with high performance.

The house is designed to achieve an 87% reduction in source energy use when compared to the 2009 Building America Benchmark. This design features high-R walls, roof, and foundation along with a high efficiency mechanical system. Supplementing the high performance enclosure and mechanical system is a 7 kW PV array installed on the south facing roof. This 87% energy use reduction is equal to HERS 18 and a \$4,700 annual utility bill savings to the homeowner.

The Concord Cape is not only part of the Building America Program, but is also registered in Builders Challenge and in USGBC's LEED for Homes program, designed to achieve Platinum certification.



### **Project Team:**

Synergy Companies Construction, LLC, Minglewood Designs, Building Science Corporation

#### Location:

Concord, Massachusetts

### Description:

4,322 ft<sup>2</sup> 5 bedroom, 4 bath, 2-story plus finished basement single family home

# **Completion Date:**

June 2010

### **Estimated Annual Energy Savings:**

\$4,700 per year (87% energy use reduction compared to the Building America Benchmark)

### **Project Website:**

www.concordcape.posterous.com




**Building Science Corporation 30 Forest Street** Somerville, MA 02143 www.buildingscience.com

## BUILDER PROFILE



Synergy Companies Construction, LLC specializes in zero and low energy new construction, Deep Energy Retrofits, remodeling, customized efficient insulating, weatherproofing and solar energy systems for both residential and commercial projects.

# PARTICIPATING PROGRAMS & CERTIFICATIONS





U.S. Green Building Council LEED® for Homes




U.S. Environmental Protection Agency ENERGY STAR® Program

# EnergySmart Home Scales Meets The Builders Challen ENERGY MEGAN

### DESIGN

### PARAMETRIC STUDY



Early in the design process, the the Airtight Drywall Approach for walls project team worked to integrate and ceilings, high density spray foam architectural, structural, mechanical components into the plans at windows and doors and taping the and specifications. Various enclosure XPS insulation joints on the basement assemblies and mechanical systems walls. For additional airtightness, the were modeled. The models were builder chose to also tape the foil-faced then used as a tool in deciding which polyisocyanurate installed on the exterior parameters were most cost effective walls. The actual tested airtightness and should be included in the project. (0.07 leak ratio) is represented in the See the Parametric Study above for chart above. included measures.


goal of a 50% energy savings when compared to the Building America Benchmark, exceptional airtightness was specified. And in order to achieve the drawings. These methods included temperatures.

at rim joists, backer rod and sealant

A highlight of the mechanical system In order to go above and beyond the design is the dual fuel heating system which includes both a heat pump as well as a high efficiency gas furnace. During the heating season, the heat pump is more efficient at milder outdoor this level of airtightness, multiple temperatures while the furnace is methods of air sealing were detailed in more efficient at lower, colder outdoor

















## **ENCLOSURE DESIGN**

- Roof Assembly: Vented attic framed with engineered roof rafters at 24" o.c. over main house: R-60 cellulose at south side ceiling, R-63 at north side cathedralized ceiling (2" foil-faced polyisocyanurate rigid insulation between rafters and 7½" high density 2.0 pcf closed cell spray foam); unvented attic framed with dimensional roof rafters at 24" o.c. over breakfast area and dormers: R-63 high density 2.0 pcf closed cell spray foam.
- **Wall Assembly:** 2x6 wood stud walls at 24" o.c. with R-45 wall insulation: cellulose (R-19), 4" foil-faced polyisocyanurate insulating sheathing (R-26), 3/4" furring strips and fiber cement siding installed on exterior, 1/2" drywall installed on interior.
- **Window Specifications:** Marvin Windows and Doors double-hung, triple pane, spectrally selective, Low-E: U=0.24, SHGC=0.23.
- Air Sealing: Maximum 0.15
  CFM50 per ft2 of enclosure area.
  Spray foam at rim joist and breakfast area and dormer roofs, airtight drywall approach used in wall assembly, taped XPS insulation on basement walls. Adhesives and sealants used between framing members, around windows and doors, and at all mechanical and electrical penetrations through the enclosure.
- **5** Foundation Assembly: 2" XPS (R-10) and stud wall with fiberglass batt insulation (R-12) installed on wall, 2" XPS (R-10 installed below slab.

### MECHANICAL DESIGN

Heating and Cooling: 195% AFUE gas furnace and 2 3-ton 8.2 HSPF/15.5 SEER heat pump split system with hybrid heat.

**Ventilation:** 3 Heat recovery ventilator (HRV) balanced ventilation system.

**DHW: 3** 0.94 EF gas condensing tankless water heater with drainwater heat recovery. **4** 

Local Exhaust Ventilation: Intermittent spot exhaust provided in bathrooms and kitchen.

**Space Conditioning** 

**Distribution:** Two zone system with sheet metal trunks and runouts located in conditioned space. Ducted return from entry hall and master bedroom with transfer grilles above bedrooms doors.

**Thermostat:** Programmable thermostat

Lighting: All CFLs in light

fixtures 5

**Appliances:** All ENERGY STAR®

appliances 6

### **CONSTRUCTION**


Before construction began, BSC held a pre-construction meeting with the builder, client, and LEED for Homes Provider. The purpose of this meeting was to review the drawing set to ensure all team members understood the design intent as well as how the design details affected house performance and third-party certification goals. Third-party certifications included LEED for











During the 10-month construction period, the project team visited the site regularly to answer questions from the builder and to document construction. The Durability Checklist, a document created during design, was used during each site visit to ensure critical details were being implemented. The checklist









addressed items including water management, air barriers, mechanical system installation, landscaping and pest control. BSC conducted a walkthrough with the homeowner and the builder to review the systems in the house to ensure it would be operated as designed to achieve maximum energy savings. A Homeowner's Manual was also given to the homeowner to use as a reference should any questions arise.



### **TESTING**

Concord Cape performance testing was done at both the rough-in stage as well as after construction was complete. At the time of the rough-in testing, the following had been installed: all windows and doors, high density spray foam at rim joists and unvented roofs (breakfast area and dormers), second floor ceiling drvwall. taped exterior insulation. sheet metal ductwork and mechanical equipment in the basement. The blower door test result was 1019 CFM50, which is equal to 0.13 CFM50 per ft<sup>2</sup> of enclosure area and 1.44 ACH50. Even before the Airtight Drywall Approach was implemented on the walls, the Concord Cape met the specified airtightness. Final performance testing revealed an even more airtight house with the following blower door test results: 505



CFM50, equal to 0.07 CFM50 per ft<sup>2</sup> of energy use. In addition to the utility enclosure area and 0.72 ACH50. Duct bills, the team will install and monitor a leakage to outside was measured at 18 comprehensive circuit-by-circuit home CFM25.

### **MOVING FORWARD**

BSC is planning to collect monthly gas and electricity bills from the homeowner for at least one year. Actual energy use will then be compared to predicted



bills, the team will install and monitor a comprehensive circuit-by-circuit home energy monitoring and management system. The system displays electricity use by individual circuit so you can see real-time and historical information on specified circuits including major appliances, heating and cooling equipment, home offices and entertainment areas.

### DESIGN HIGHLIGHT: 7 KW PV ARRAY WITH MICROINVERTERS

With the site oriented North – South, the Concord Cape roof is ideal for the design and implementation of a photovoltaic array. A large low-slope (4:12) south facing roof allows light into the Master Bedroom and provides a large enough area for a 7 kW PV array. Each of the 30 solar modules has its own microinverter which converts DC power to grid-compliant AC power. Real-

time solar collection is displayed on the Energy Management Unit which sends the performance data to the microinverter manufacturer's website. Here the homeowner can log-in to see both real-time and historical data for each individual module as well as for the entire system.









This case study has been prepared by Building Science Corporation for the Department of Energy's Building America Program, a private/public partnership that develops energy solutions for new and existing homes. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof.

AMPRICA STATE OF Energy

For more information about Building America go to www.buildingamerica.gov



For more information about this or other case studies by Building Science Corporation and the Building America Program go to: www. buildingscienceconsulting.com/services/building-america.aspx.

